


Summary of Source Bulk Sampling

CLIENT: SMMUSD
PROJECT NO: SMSD-20-9871
PROJECT: Santa Monica High School PCB survey
Date: 11/16/2020

History Building

Sample Number	Sample Description	Sample Location	Material Location	Total PCBs (ppm)
H-58	Step caulking	Middle step	Northwest interior basement stairway to 1st floor	762
H-59	Step caulking	Bottom step	Northwest interior basement stairway to 1st floor	167
H-60	Step caulking	Top step	Northwest interior basement stairway to 1st floor	74.8
H-70	Stairway flooring with glue	1st floor	Northwest stairway	382
H-71	Stairway flooring with glue	1st floor	Northeast stairway	118
H-78	Stair flooring	Top step near south entrance	Exterior entrance stairs non-skid flooring	71.2
H-125	Concrete 3"	Northwest stairway base to 1st floor	Northwest interior basement stairway to 1st floor	2.9
H-126	Concrete 1"	Northwest stairway base to 1st floor	Northwest interior basement stairway to 1st floor	4.19
H-129	Concrete 3"	Northwest interior basement stairway to 1st floor, top step	Northwest interior basement stairway to 1st floor	1.22
HC-01	Concrete core 1/2"	Stairs to 1st floor	Northwest stairwell	71.2
HC-04	Concrete core 1/2"	Stairs to 1st floor	Northwest stairwell	72.3
HC-07	Concrete core 1/2"	Northeast stairwell	Northeast stairwell	31.5
HC-08	Concrete core 3/4"	Northeast stairwell	Northeast stairwell	1.58
HC-09	Concrete core 1"	Northeast stairwell	Northeast stairwell	2.92



This figure was created in color. Significant information may be lost if copied in black and white.

Legend

- Delineation/ Source - TSCA
- Delineation/ Source - Detected above PQL
- Delineation/Source - ND

Homogeneous Figure - History Building, Basement Level

Santa Monica High School
601 Pico Boulevard
Santa Monica, California



N|V|5

ALTA
ENVIRONMENTAL

3777 Long Beach Blvd. Annex Bldg. Long Beach, California 90807
P: (562) 495-5777 ♦ F: (562) 495-5877 ♦ www.altaenviron.com

DATE: Feb 2021

Project No.: SMSD-20-9871


Summary of Source Bulk Sampling

CLIENT: SMMUSD
PROJECT NO: SMSD-20-9871
PROJECT: Santa Monica High School PCB survey
Date:

Cafeteria Building

Sample Number	Sample Description	Sample Location	Material Location	Total PCBs (ppm)
C-86	Seam caulking	Northwest corner	Exterior wall seam between concrete and stucco	14100
C-05	Stucco core 1"	Exterior northwest corner	Exterior wall seam between concrete and stucco	18.4

Note: No exterior door caulking observed.



This figure was created in color. Significant information may be lost if copied in black and white.

Legend

- Delineation/ Source - TSCA
- Delineation/ Source - Detected above PQL
- Delineation/Source - ND

Sample Location Figure - Cafeteria Building

Santa Monica High School
601 Pico Boulevard
Santa Monica, California





3777 Long Beach Blvd. Annex Bldg. Long Beach, California 90807
P: (562) 495-5777 ♦ F: (562) 495-5877 ♦ www.altaviron.com

DATE: Feb 2021

Project No.: SMSD-20-9871